


## Side View




<u>Cone</u> 28" - 3,600 lb





Riser Weights
12" - 1,300 lb
16" - 1,750 lb
24" - 2,600 lb
32" - 3,450 lb
36" - 3,900 lb
48" - 5,200 lb
60" - 6,500 lb
64" - 6,900 lb

Top View



# Monolithic base \* 60" 8"

Base Weights
12" - 4,150 lb
16" - 4,500 lb
24" - 5,450 lb
32" - 6,300 lb
48" - 8,000 lb
60" - 9,300 lb
64" - 9,750 lb
71" - 10,500 lb

# **Approved for Production**

Project:	Date:	
Quantity:	By:	

# BARGER

### **Specifications**

**Concrete:** 5,000 psi minimum 28 day compressive strength

**Reinforcing:** Per ASTM C478 with design calculations performed by a Licensed P.E. Minimum

2" cover of all reinforcing steel.

Pipe Penetrations: All pipe penetrations are placed according to job requirements.

**Pipe Seals:** All pipe boots will meet ASTM C 923. **Sealant:** Sealant used will meet ASTM C 990.

**Steps:** On 16" center unless otherwise specified.

**Preformed Invert:** As required by plans or governing specifications.

# 60" I.D. precast concrete manhole pieces ASTM C-478 Compliant

C.R. Barger & Sons, Inc. P.O. Box 370 - Kingston TN 37763 Phone 888.882.5860 - BargerAndSons.com

7.162021

Drawn By: Eric Barger

Updated: 5.042022