


# Top View



## Side View




#### **End View**




- Corporation Stop AY  $\frac{3}{4}$ " 74101BCAF (300 PSI)
- Meter Setter AY <sup>3</sup>/<sub>4</sub>" 720-207WDDD 33 X992
- Brass nipples  $AY \frac{3}{4}$ " x 4"  $AY \frac{3}{4}$ " x 18" (poly wrap nipple through wall)
- Multi-purpose adapter  $AY \frac{3}{4}$ " 720-3D3 ASY
- 29" x 59" opening single leaf aluminum door, pedestrian rated (300 lb/ft^2)
- 4" or 6" D.I.P. Class 52 / PR 350
- 2" drain hole

# Component Detail



### Pipe detail for taps



# **Approved for Production**

| Project:  | Date: |  |
|-----------|-------|--|
|           |       |  |
| Quantity: | Rv:   |  |

#### **Specifications**

Concrete: 5,000 psi minimum strength (28 day)

By:

**Pipe Penetrations:** All pipe penetrations are placed according to job requirements.

# 4-Gang 3" Meter Vault **Barger Standard**

C.R. Barger & Sons, Inc. P.O. Box 370 - Kingston TN 37763 Phone 888.882.5860 - BargerAndSons.com

Date: 6.022022

Drawn By: Eric Barger

Approx. Empty Vault Weight: 3,100 lbs.